4	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.6) PW, P & IWTD - SR 2013-14)	Cum							
	Drain		1	250.00	0.45	0.08	8.44		
			2	250.00	0.20	0.10	10.00		
	Basic Rate	4425.00					**18.44**	4690.50	**86481.00**
	Add Area Weightage 6%	265.50							
	Total	**4690.50**							
5	Refixing stone slabs of drains and pointing in CM 1:3 etc complete Page No. 28/ Item No.5.33/ PWD SR 2013-14	**Sqm**							
		Qty Vide Iteam No 2					**135.00**		
	Basic Rate	64.85					135.00	70.04	**9455.00**
	Add Area Weightage 8%	5.19							
	Total	**70.04**							
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 thick (P. 27 I. 5.31.1) Page No. 28/ Item No. 5.31/ PWD SR 2013-14	**Sqm**							
	Drain		1	250.00	-	0.90	**225.00**		
		Deduct Availabe Qty Vide Iteam No 2					**135.00**		
	Basic Rate	318.00					90.00	343.44	**30910.00**
	Area Weightage 8%	25.44							
	Total	**343.44**							
7	KSRB 5-14 : Providing and constructing precast **concrete solid blocks** with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size **40x20x20** cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. **Page No. 27/ Item No. 5.27/ PWD SR 2013-14**	**Sqm**							
	Drain		2	250.00	0.40		200.00		
	Basic Rate	856.00					**200.00**	924.48	**184896.00**
	Add Area Weightage 8%	68.48							
	Total	**924.48**							
8	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm							
			1	250.00	0.90		225.00		
	Data Rates Approved by CE DZ						**225.00**	1600.00	**360000.00**